MANAGEMENT OF CONSTRUCTION WASTE IN THE CONTEXT OF PROJECT MANAGEMENT

Gonalagodage Nandun Dakshika Tillakaratne

(03/9774)



Degree of Master of Science in Project Management

Department of Building Economics

University of Moratuwa Sri Lanka

December 2012

MANAGEMENT OF CONSTRUCTION WASTE IN THE CONTEXT OF PROJECT MANAGEMENT

Gonalagodage Nandun Dakshika Tillakaratne

(03/9774)



Thesis submitted in partial fulfillment of the requirement for the degree of Master of Science in Project Management

Department of Building Economics

University of Moratuwa Sri Lanka

December 2012

DECLARATION

I declare that this is my own work and this thesis does not incorporate without acknowledgement any material previously submitted for a Degree or Diploma in any other University or Institute of higher learning and to the best of my knowledge and belief it does not contain any material previously published or written by another person except where the acknowledgement is made in the text.

Also, I hereby grant the University of Moratuwa the non-exclusive right to reproduce and distribute my thesis, in whole or in part, in print, electronic or other medium. I retain the right to use this content in whole or part in future works.

Signature		Date
٩	University of Moratuwa, Sri Lanka. Electronic Theses & Dissertations www.lib.mrt.ac.lk	
The above candidate has ca	rried out research for the Master	s under my supervision.
Signature of the Supervisor		Date

ACKNOWLEDGEMENT

This thesis would not have been possible without the assistance, support, and encouragement of many wonderful people to whom I wish to convey my sincere appreciation.

First and foremost, I am indebted to Senior Lecturer – H.S. Jayasena and Prof. R. Rameezdeen; my dissertation supervisors who gave me enormous guidance and support continuously throughout this process and it took me to my highest. My humble gratitude goes to them for all the support and guidance provided.

I would like to express my sincere thanks to Senior Lecturer, Dr. Sepani Senaratne and Head of the Department of Building Economics - Mr. Indunil Seneviratne who gave me there fruitful advice for the success of this thesis.

I am especially grateful to all those who gave their fullest support in providing me the data of newly erected buildings in the Colombo district.

Finally, I am indebted to my family members and colleagues for their spiritual and emotional reinforcement throughout the study.

ABSTRACT

Construction waste is a Project Management problem occurring at site level. In the absence of guidelines, Project managers find it difficult to benchmark their site performance in waste management. On the other hand, how much waste a construction site would generate had been a question for local authorities in Colombo local authority limits. The volume of construction waste could be ascertained using the norm construction waste index at the stage of receipt of the new building applications by that particular local authority. The scarcity of dumping sites in Colombo Local Authority level is the issue behind this problem.

Project managers and municipal commissioners conducted a study to determine usable waste indices. Data was collected from fifty recently completed construction projects within the Colombo district. Gross floor area based waste index was calculated for each project and those indices were statistically analysed to find conclusions.

The study shows that the Colombo district local authorities should use the norm construction waste index of 0.114 in assessing the building applications for Construction of new buildings. However, necessary steps should be taken to influence and motivate builders (specifically their project managers) to reduce the waste at least to average levels. In addition, based on good track records of the builder (if available), they can deviate from this norm to the average level of 0.043. The construction waste index of 0.016 is an achievable target and any additional waste generated can be discriminated by way of acquiring an additional fee or taxes. Further, these recommendations are identified in order to support the efforts to make the building industry a better, greener and social responsible industry.

Keywords: Construction Waste, Waste Index, Colombo Local Authority level

TABLE OF CONTENTS

		Page
Declara	ation of the candidate & Supervisor	i
Acknov	wledgement	ii
Abstrac	et	iii
Table o	of contents	iv
List of	figures	vi
List of	tables	vii
List of	abbreviations	viii
List of	Appendices	ix
СНАР	TER ONE	1
1.0	Introduction	1
1.1	Background	1
	1.1.1 Construction waste at site (project level)	4
	1.1.2 Construction and demolition waste at National Level	
1.2	Significance of the study	5
1.3	The objectives of the study	6
1.4	Methodology	6
1.5	Limitations	7
1.6	Organization of the Thesis	7
СНАР	TER TWO	9
2.0	Literature Survey	9
2.1	Management of Construction Projects	9
2.2	Definition of Construction Projects	9
2.3	Definition of Project Management	10
2.4	The Traditional Triple Constraint	11
2.5	Prediction of Waste Quantity	15
2.6	Project Management on the Problem of waste Management	15
2.7	Solid Waste Problem	16

	2.8	Solid Waste	17	
	2.9	Construction & Demolition (C&D) Waste	17	
	2.10	Definition of construction waste	18	
	2.11	Sources of construction waste	19	
	2.12	Effects of construction waste	21	
	2.13	Construction waste management & Importance of waste minimization	23	
	2.14	Construction waste index	24	
•	СНАРТ	TER THREE		
	3.0	Methodology	25	
	3.1	Methodology of the study		
		3.1.1 Area selection	25	
		3.1.2 Data collection	25	
		3.1.2.1 Primary data	25	
		3.1.2.1.1 Observation	26	
		3.1.2.1.2 Interviews	26	
		3.1.2.2 Secondary data	26	
	3.2 C	Collected data Electronic Theses & Dissertations	27	
	3.3 F	indings	28	
	3.4 N	3.4 Method of Analysis		
C		TER FOUR		
	4.0	Data Analysis		
	4.1	Introduction		
	4.2	The advantages of creating a norm for construction waste index		
	4.3	Quantitative Techniques used for data analysis		
	4.4	Analysis of data	32	
		4.4.1 Composition of the Sample		
		4.4.2 Setting a Range	33	
	4.5	Statistical Interpretation	36	

CHAP'	TER FIVE	37
5.0	Conclusions & Recommendations	37
5.1	Conclusions	37
5.2	Recommendations	39
5.3	Further Studies	39
REFEI	RENCE LIST	40
APPL	NDICES	44



LIST OF FIGURES

		Page
Figure 1.1 –	Flow chart of the flow of dissertation.	8
Figure 2.1 –	Waste Management hierarchy	23
Figure 4.1 –	Composition of types of buildings	33
Figure 4.2 –	Histogram of the considered data	36



LIST OF TABLES

		Page
Table 1.1 –	Status of construction waste in local authority levels	3
Table 4.1 –	Composition of the sample	32
Table 4.2 –	Details of the rejected data	33
Table 4.3 –	Data used for analysis	34



LIST OF ABBREVIATIONS

Abbreviation	Description
BRE	Building Research Establishment
C&D	Construction and Demolition
CEA	Central Environment Authority
ICTAD	Institute for construction, Training and Development
NGO	Non-Governmental Organization
PMI	Project Management Institute
Q	Quartile
UDA	Urban Development Authority
P.S.	Pradeshiya Sabha



APPENDICES

	P	age
Appendix – A:	Data collection sheet	. 44

