# GUIDELINES FOR CONSTRUCTION OF LOW VOLUME CONCRETE ROADS IN SRI LANKA

N.A.A. Priyantha

(06/8858)

Dissertation submitted in partial fulfillment of the requirements for the Master of Engineering in Highway and Traffic Engineering

Department of Civil Engineering

University of Moratuwa Sri Lanka

University of Moratuwa

95715

April 2010

I

#### **ABSTRACT**

The purpose of the study was to develop guidelines for construction of low volume concrete roads in Sri Lanka. It describes the most suitable way of preparation of subgrade, subbase, mixing and pouring of concrete, construction of shoulder and maintenance of concrete pavements. A survey was carried out to study current concrete road construction practice and identify their advantages and disadvantages. Incorrect construction of contraction joints were also observed in most of roads during the site visit and special attention was given to develop a new method to construct them. An experiment was carried out to study effective curing using coir dust and saw dust. The spraying Frequency of water for curing was determined through that experiment. A special tool was developed to measure surface undulation on local concrete pavements. A comparison of various kinds of concrete producing methods and their performance were included in the report. "Check lists" have been introduced for most of activities to enhance the quality of the pavement construction. Quality and cost control techniques in the field of low volume concrete road construction in Sri Lanka are also described.

#### Declaration of the candidate

"I declare that this is my own work and this thesis/dissertation does not incorporate without acknowledgement any material previously submitted for a Degree or Diploma in any University or other institute of higher learning and to the best of my knowledge and belief it does not contain any material previously published or written by another person except where the acknowledgement is made in the text"

Signature of the Candidate

30 03 2010





# Declaration of the supervisor

"I have supervised and accepted this thesis for the submission of the degree"

Supervisor – Professor J.M.S.J. Bandara Department of Civil Engineering University of Moratuwa Sri Lanka.

Date





#### Acknowledgement

I gratefully acknowledge my thanks to my supervisor Professor J.M.S.J. Bandara University of Moratuwa for valuable comments and suggestions throughout the work on this research.

Professor W.P.S. Dias, Head of the Department of Civil Engineering, University of Moratuwa and all the staff members of Transportation Engineering Division of University of Moratuwa deserve special gratitude for their help in this research possible.

I wish to place on record my gratitude to the Road Development Authority for sponsoring and granting leave to follow this course.

Finally, I acknowledge and thank all those who have provided data and information to me in performing this research study.

www.lib.mrt.ac.lk

# **TABLE OF CONTENTS**

			Page
Declaration of the	candida	te	i
Declaration of the s	supervi	sor	ii
Acknowledgement			iii
Abstract			iv
Table of content			v
List of Figures			viii
List of Tables			ix
List of abbreviations			xi
List of annexure		University of Moratuwa, Sri Lanka. Electronic Theses & Dissertations	xi
Chapter 1:	Intro	oduction lib.mrt.ac.lk	1
	1.1	Background	1
	1.2	Present Study	2
Chapter 2:		iew of Road User Inconveniences due to d Rehabilitation Projects in Sri Lanka.	6
	2.1	Air Pollution	6
	2.2	Noise Pollution	10
	2.3	Traffic Delays	12
	2.4	Effects of Work Site User Accessibility	15
	2.5	Effects to Water Ways and Road Drains	17

	2.6 Interruptions to U	Jtility Services	18
Chapter 3:	Analysis of User Respo	onse of the Survey for Road User	21
	3.1 Survey Data Ana	ılysis	25
	3.2 Summary of Use	r Category Analysis	39
	3.3 Survey Data Ana	llysis Using SPSS Software	40
	3.4 Summary of Soft	ware Data Analysis	46
Chapter 4:	Strategies to Minimize Road Rehabilitation	User Inconvenience During	49
	4.1 Strategies to Min	imize Air Pollution	49
	<u> </u>	imize Noise Pollution	57
	4.3 Strategies to Min	imize Traffic Delays	62
	4.4 Strategies to Min Site Accessibility	imize Disturbing Work	81
	4.5 Strategies to Min Ways and Drains	imize Disturbing to Water	84
	4.6 Strategies to Min Services	imize Interruption to Utility	86
Chapter5:	Conclusions and Recor	nmendations	88
	5.1 Conclusions		88
	5.2 Recommendation	ns	89
Reference List			90
Annendix A:			02

Appendix B:	93
Appendix C:	94



# LIST OF FIGURES AND TABLES

#### LIST OF FIGURES

		Page
Figure 2.1	Laying aggregate base course layer on Colombo –Kandy road	7
Figure 2.2	Full road closure for culvert concreting at Beliyatta - Walasmulla road	12
Figure 2.3	Half road closure for culvert construction at Beliyatta - Walasmulla road	13
Figure 2.4	Unsafe environment created due to Kadawatha road project	15
Figure 2.5	No space is provided for pedestrians during construction of culvert at Weeraketiya – Middeniya road	16
Figure 2.6	Poor accessibility during construction at Colombo – Kandy road at Kadawatha town	17
Figure 3.1	University of Moratuwa, Sri Lanka.  Type of inconvenience perceived to users Dissertations	25
Figure 3.2	Construction activities perceived to residence	27
Figure 3.3	Construction activities perceived to pedestrian	30
Figure 3.4	Construction activities perceived to commercial parties	33
Figure 3.5	Construction activities perceived to drivers	35
Figure 3.6	Construction activities perceived to passenger	38
Figure 4.1	Typical layout of tire wash	55
Figure 4.2	Cross section of a typical tire wash	56

### LIST OF TABLES

Table 2.1	Noise levels of construction equipments	10
Table 2.2	Accident data at Kadawatha Town	14
Table 3.1	Analysis of user response	22
Table 3.2	Summary of the field survey	25
Table 3.3	Type of activities affect for inconvenience to residence people.	27
Table 3.4	Type of activities affect for inconvenience for pedestrians	30
Table 3.5	Type of activities affect for inconvenience for commercial parties	33
Table 3.6	Type of activities affect for inconvenience for drivers	35
Table 3.7	Type of activities affect for inconvenience for passengers	37
Table 3.8	Air pollution vs Material storing cross tabulation	40
Table 3.9	Air pollution vs Transporting cross tabulation	40
Table 3.10	Air pollution vs Machine Operating cross tabulation	41
Table 3.11	Air pollution vs Material Laying cross tabulation	41
Table 3.12	Air pollution vs Site Clearing cross tabulation	41
Table 3.13	Air pollution vs Surfacing cross tabulation	41
Table 3.14	Air pollution vs incidental construction cross tabulation	42
Table 3.15	Activities caused to air pollution	42
Table 3.16	Activities caused to noise pollution	43
Table 3.17	Activities caused to traffic delays	43
Table 3.18	Activities caused to disturbing to accessibility	44
Table 3.19	Activities caused to drainage problems	45
Table 3.20	Analysis users respond against inconvenience and construction activities	46

Table 4.1	Traffic data at Bandarawaththa	7.5
Table 4.2	Calculation of saving due to traffic delays	76
Table 4.3	Calculation of saving due to freight transports	77
Table 4.4	Calculation of saving of vehicle operating cost	78
Table 4.5	Accident data at Kadawath Town	79
Table 4.6	Number of accidents due to Kadawatha town project	79
Table 4.7	Calculation of cost of saved by accidents	79
Table 4.8	Calculation of cost of saving due to vehicular emission	80



# List of Abbreviations

Abbreviation	Description
AASETO	American Association of State Highway and Transportation Officials
800	Isill of Quantities
CEÁ	Central Environmental Authority
dB	Decibles
10TAD	Institute for Construction Training and Development
1.118	Left Hand Side
\√{\forall ^*}	Maintenance and Protection of Traffic
AMM)	Medium Density Overlayy of Moratuwa, Sri Lanka.
RHS	Electronic Theses & Dissertations king Hand Side www.lib.mrt.ac.lk
SELRIC	Sri Lanka Land Reciamation and Development Corporation
VIX.	Vehicle Operating Cost
	LIST OF ANNEXURE

voviex.are	Description	Page
Аменчите - А	National Environmentel Act.	92
rmexare - B	Format of survey form	93
Albertaire - C	Data analysis of SPSS software	94