UNIVERSITY OF MORATUWA

A REVIEW OF STANDARD METHOD OF MEASUREMENTS OF BUILDING WORKS - SRI LANKA (Revised Edition SLS 573)

RV



SUPERVISED BY DR. G. W. KODIKARA

DEPARTMENT OF CIVIL ENGINEERING UNIVERSITY OF MORATUWA, MORATUWA, SRI LANKA.



22

UNIVERSITY OF MORATUWA

පුස්කකාලය ඉතිරෙටුව විශ්ව විදපාලය. ශුී ලංකාව ඉතාරටුව,

A REVIEW OF STANDARD METHOD OF MEASUREMENTS OF BUILDING WORKS - SRI LANKA (Revised Edition SLS 573)

PERMANENT REFERENCE NOT TO BE REMOVED FROM THE LIBRARY.



SUPERVISED BY DR. G. W. KODIKARA

69.008.19

DEPARTMENT OF CIVIL ENGINEERING UNIVERSITY OF MORATUWA, MORATUWA, SRI LANKA.

63053

CONSTRUCTION & STRUCTURAL ENGINEERING DEPARTMENT OF CIVIL ENGINEERING UN. MRSITY OF MORATURY

A REVIEW OF STANDARD METHOD OF MEASUREMENTS OF BUILDING WORKS - SRI LANKA (REVISED EDITION SLS 573)

BY

C. DILKUMAR

A REPORT SUBMITTED IN PARTIAL FULFILLMENT OF THE REQUIREMENT FOR THE DEGREE OF



THE FACULTY OF ENGINEERING DEPARTMENT OF CIVIL ENGINEERING

PERMANENT REFERENCE NOT TO BE REMOVED FROM THE LIBRARY.

SUPERVISED BY DR. G. W. KODIKARA

University of Moratuwa November 1994

ABSTRACT

Sri Lanka did not have a Standard Method of measurement of Building works until 1982. Various organisations have been using different methods. These were modified versions of SMM 4 and SMM 5 of RICS (U.K.), SMM prepared by HAW in 1968 and other methods developed by the organisations to suit the practices of local industry. To achieve the uniformity in the method of measurement of building works in the industry, the standard methods of measurement of Building works, SLS 573, was introduced in 1982.

Now after twelve years ICTAD has revised this document and named it as SLS 573, Revision: 1994. This research was to identify the differences between the revision and the first SLS 573 and to get the responses of the industry regarding the major changes. In order to get the responses of the industry, questionnaires were sent to twenty four consultants and contractors. Also some formats of bills of quantities were studied in order to get the good aspects of them.

Based on these responses it can be said that SLS 573; revision:1994 is fairly accepted with some improvements. Due to the limitations of time only the major changes as defined in this study were taken into consideration and it is worthy to undertake a study to observe whether the industry accepts all the differences given in Appendix A.



ACKNOWLEDGEMENT

I wish to express my sincere gratitude to Dr. G.W. Kodikara, the project supervisor, for the proper guidance provided throughout the project without which this project would not have been a success.

It is my duty to remeber with gratitude the course Director Prof. S.R.De S. Chandrakeerthy and his academic staff for their valuable contributions given to complete Master Degree Program successfully.

I also thank Mr. H.D. Chandrasena, the chief quantity surveyor of the State Engineering Corpration for providing me with valuable information which led to the success of the project.

I wish to extend my gratitude to all the state and private organisations in the construction industry for helping me in the collection of data.

Finally my special thanks go to Dr. Asoka Perera for guiding me in the latter stages of the project, particularly in writing the project report.



CONTENTS

	<u>Description</u>	Page	
		_	
	Abstract	i	
	Acknowledgement	ii	
	List of Abbreviations	v	
	List of Tables	vi	
	List of Fugures	vii	
1.	Introduction	1	
1.1 1.2	Background Objectives	1	
1.3	Progra University of Moratuwa, Sri Lanka.	1	
	Electronic Theses & Dissertations www.lib.mrt.ac.lk	1	
	1.3.2 WWW.IID.Mrt.ac.IK 1.3.3	2 2 2	
	1.3.4 Documentation	2	
1.4	Main Findings	2 2	
1.5	Guide to Report 1.5.1 Chapter Two - Method of Measurement		
	1.5.2 Chapter Three - Format of the Bill of Quantities	2 2	
	1.5.3 Chapter Four - Standard Method of Measurement of	3	
	Building Works SLS 573 1.5.4 Chapter Five - Response for the SLS 573 revision;1994	3	
	1.5.6 Chapter Six - Conclusions and Recommendations		
2.	Method of measurement	3 4	
2.1	Introduction	4	
2.2 2.3	Standard method of measurement of Building works in the United Kingdom.6 Standard method of measurement of Building works in Sri Lanka.	11	

	3. Format of the Bill of Quantities.			14
	3.1	Introduction		14
	3.2	Elemental Bill		
	3.3	Sectionalised Trades Bills.		
	3.4	Operational Bill		
	3.5	Bill of quantities (operational format)		
	3.6	The BPF system -	Shedule of Activities.	18
	3.7	Standard method of	f measurement	20
	4.	Standard method of	f measurement of Building works: SLS 573.	21
	4.1	Introduction		21
	4.2	LS 573:1982 and SLS 573 revision:1994	22	
	4.3	Comparision between	en SLS 573:1982 and SLS 573 revision:1994.	24
	4.4	Major differences between SLS 573:1982 and SLs 573 revision:1994.		25
	5.	Response for the Sl	LS 573 revision:1994	29
	5.1	Introduction		29
	5.2	Response from grade I contractors.		
	5.3	Respons ^	• ••	34
	5.4	Respons 👸	University of Moratuwa, Sri Lanka.	38
	5.5	Summar	Electronic Theses & Dissertations	41
	6.	Conclus	www.lib.mrt.ac.lk	49
	7.	Recommendations		50
		References		51
		Appendix A		52
		Appendix B		62

LIST OF ABBREVIATIONS

B.O.Q. - Bill of Quantities

ICTAD - Institute for Construction Training and Development.

R.I.C.S. - Royal Institute of Chartered Surveyors.

C.C.P.I. - Coordinating committee for project information.

N.F.B.T.E. - National Federation of Building Trade Empoyers.

B.E.C. - The Building Employers Confederation.

S.M.M. - Standard Method of Measurement.

S.L.S. - Sri Lankan Standard

S.E.C.

University of Moratuwa, Sri Lanka.
Electronic Theses & Dissertations
www.lib.mrt.ac.lk

mm - milli metre

cm - centi metre

m³ - cubic metre

m² - square metre

LIST OF TABLES

Table No.	<u>Description</u>	Page No.
4.1	Major work sections in SLS 573;1982 and SLS 573 revision;1994	23
4.2	Major differences in SLS 53;1982 and SLS 573 revision;1994	26
5.1	Response from Grade I Contractors	30
5.2	Views of Grade one Contractors	31
5.3	University of Moratuwa, Sri Lanka. Electronic Theses & Dissertations	35
5.4	www.lib.mrt.ac.lk	36
5.5	Response from Consultants	39
5.6	Views of Consultants.	40
5.7	Summary of % agreement for change	44

LIST OF FIGURES

Fig.No.	Description	Page No.	
5.1	Response from Grade I Contractors	31	
5.2	Response from Grade II Contractors	35	
5.3	Response from Consultants	37	
5.4	University of Moratuwa, Sri Lanka. Electronic Theses & Dissertations	42	

